DNV·GL

Certificate No:
TAE00003RC

TYPE APPROVAL CERTIFICATE

This is to certify:

That the Electric Power Cable

with type designation(s)
CJV82/DA/SA, CJV92/DA/SA

Issued to
Yangzhou Guangming Cable Co., Ltd
YANGZHOU, JIANGSU, China

is found to comply with
DNV GL rules for classification – Ships, offshore units, and high speed and light craft

Application :

Product(s) approved by this certificate is/are accepted for installation on all vessels classed by DNV GL.
Rated voltage (kV) **0,6/1**
Temp. class (°C) **90**

Issued at **Hamburg** on **2019-10-01**
This Certificate is valid until **2024-09-30**.
DNV GL local station: **Nanjing**

Approval Engineer: **Carsten Hunsalz**

for **DNV GL**

Arne Schaarmann
Head of Section

This Certificate is subject to terms and conditions overleaf. Any significant change in design or construction may render this Certificate invalid.
The validity date relates to the Type Approval Certificate and not to the approval of equipment/systems installed.

© DNV GL 2014. DNV GL and the Horizon Graphic are trademarks of DNV GL AS.

Job Id: **262.1-031376-1**
Certificate No: **TAE00003RC**

Product descrProduct description

XLPE insulated shipboard power cables

Rated voltage:	0,6/1 kV
Maximum operating conductor temperature:	90° C
Conductor:	Tinned stranded copper
Insulation:	XLPE
Inner sheath:	V – PVC ST2
Armour / braid:	8 – Tinned copper wire braid 9 - Galvanized steel wire braid
Outer sheath:	2 – ST2

No. of cores:	Nominal cross section mm²
1	1 up to 300
2	1 up to 120
3	1 up to 185
4 to 37	1, 1.5, 2.5

Application/Limitation

General power and lighting. Control.

The following applies to SA type cables only:

The requirements of SOLAS Amendments Chapter II-1, Part D, Reg. 45, 5.2 (provision to be taken to limit Fire Propagation along Bunches of Cables or Wires) are fulfilled without any additional measures.

Flame retardant Cat. A.

Type Approval documentation

Test report :	CT 03-1054-2; CT2001-0022-1; CT2001-0022-2; CT2001-0022-3; CT04-1160-1; CT09-1387A-1; CT14-1767-2
Specification:	No. GL/TZ00020; GL/TZ00021; GL/TZ00022; GL/TZ000122; GL/TZ000123; GL/TZ000124

Tests carried out

Standard	Release	General description	Limitation
IEC 60092-350	2014-08	General construction and test methods of power, control and instrumentation cables for shipboard and offshore applications	
IEC 60092-353	2016-09	Electrical installations in ships - Part 353: Power cables for rated voltages 1 kV and 3 kV	
IEC 60092-360	2014-04	Electrical installations in ships - Part 360: Insulating and sheathing materials for shipboard and offshore units, power, control, instrumentation and telecommunication cables.	

Standard	Release	General description	Limitation
IEC 60332-1-2	2015-07	Tests on electric and optical fibre cables under fire conditions – Part 1-2: Test for vertical flame propagation for a single insulated wire or cable –Procedure for 1 kW pre-mixed flame	
IEC 60332-3-22*	2018-07	Tests on electric and optical fibre cables under fire conditions – Part 3-22: Test for vertical flame spread of vertically-mounted bunched wires or cables – Category A	Charred portion of sample does not exceed 2,5m above bottom edge of burner.

* SA type only

Marking of product

Example:

Yangzhou Guangming Cable Co., Ltd – CJV82/SA - 0,6/1kV – size - IEC 60332-3-22* - Lot no.

* SA type only

Periodical assessment

The scope of the periodical assessment is to verify that the conditions stipulated for the Type approval are complied with and that no alterations are made to the product design or choice of materials.

The main elements of the assessment are:

- Inspection on factory samples, selected at random from the production line (where practicable)
- Results from Routine Tests (RT) checked (if not available tests according to RT to be carried out)
- Review of type approval documentation
- Review of possible change in design, materials and performance
- Ensuring traceability between manufacturer's product type marking and Type Approval Certificate.

Periodical assessment is to be performed after 2 years and after 3.5 years. A renewal assessment will be performed at renewal of the certificate.

END OF CERTIFICATE