DNV·GL

Certificate No:
TAK000016Z

TYPE APPROVAL CERTIFICATE

This is to certify:

That the Plastic Pipes, Fibre Reinforced Thermosetting

with type designation(s)
Bondstrand™ Series 2400-B91 Non-Conductive GRE Pipes & Fittings,
Bondstrand™ Series 2400C-B91 Conductive GRE Pipes & Fittings

Issued to
NOV FGS Malaysia Sdn. Bhd.
Johor, Malaysia

is found to comply with
DNV GL class programme DNVGL-CP-0070 – Type approval – Fibre reinforced thermosetting plastic piping systems
DNV GL rules for classification – Ships
IMO Resolution A.753(18). Guidelines for the Application of Plastic Pipes on Ships

Application :

For installation according to DNV GL Rules and Manufacturer's Specification, non-conductive/conductive. The piping system is approved to Fire Endurance L3 according to IMO Resolution A.753(18) and Low Flame Spread, according to ASTM D635-97.

Product(s) approved by this certificate is/are accepted for installation on all vessels classed by DNV GL.

This Certificate is valid until **2023-07-04**.

Issued at **Høvik** on **2018-07-05**
DNV GL local station: **Singapore** for **DNV GL**

Approval Engineer: **Gisle Hersvik**

Rikard Törnqvist
Head of Section

This Certificate is subject to terms and conditions overleaf. Any significant change in design or construction may render this Certificate invalid.
The validity date relates to the Type Approval Certificate and not to the approval of equipment/systems installed.

© DNV GL 2014. DNV GL and the Horizon Graphic are trademarks of DNV GL AS.

Product description

Bondstrand™ Series 2400-B91 Non-Conductive GRE Pipes & Fittings,
Bondstrand™ Series 2400C-B91 Conductive GRE Pipes & Fittings,

- Lined/Unlined, Conductive/Non-conductive. According to NOV FGS's Bondstrand Product Data: "TOTAL Series"
- Nominal internal pressure: 12 bar (with 6 times safety factor on internal pressure)
- External collapse pressure: full vacuum condition.

B91 = Piping class named according to TOTAL Specification.

Pipe Series 2400-B91/2400C-B91:

		Minimum reinforced wall thickness in mm											
Ø (mm)	**PN [bar]**	**25**	**50**	**80**	**100**	**150**	**200**	**250**	**300**	**350**	**400**	**450**	**500**
2400-B91	**12***	5.0	5.0	5.0	5.0	5.0	5.3	6.1	6.7	7.1	7.9	8.7	9.6
2400C-B91	**12***	5.0	5.0	5.0	5.0	5.0	5.3	6.1	6.7	7.1	7.9	8.7	9.6

		Minimum reinforced wall thickness in mm, incl. 0.5 mm liner						
Ø [mm]	**PN [bar]**	**600**	**700**	**750**	**800**	**900**	**1000**	
2400-B91	**12***	11.6	13.8	14.8	15.8	17.7	19.8	
2400C-B91	**12***	11.6	13.8	14.8	15.8	17.7	19.8	

* with safety factor of 6

Fittings:
Elbows, Tees, Laterals, Crosses, Reducers, Flanges, Couplers and Adaptors.

Jointing Methods:
QL, DN25 to DN100
Taper-Taper Adhesive Joint, DN150 to DN1000

Manufactured by

NOV FGS Malaysia Sdn. Bhd., PLO 202 Senai Industrial Park, Phase IV, 81400 Senai, Johor, Malaysia

DNV GL local station: Singapore

NOV FGS Malaysia Sdn. Bhd., PLO 79, Jalan Rumbia 2, Kompleks Perindustrian Tanjung Langsat, Johor, Malaysia

DNV GL local station: Singapore

Responsibility

The Company (stated on the front page of this Certificate) takes the responsibility that both design and production are in compliance with Rules, Standards and/or Regulations listed on page 1 of this certificate.

Application/Limitation

Approved only for installation of piping systems which will not be exposed to external pressure outside the pipes.

For installation according to DNV GL Rules/Standards and Manufacturer's Specification.

Maximum operating temperature +93°C.

The piping system is approved as:
- Unlined and Conductive
- Unlined and Non-conductive
- Lined and Conductive
- Lined and Non-conductive

dependent on client's needs.

Fire Endurance
The piping system is approved to Fire Endurance L3 according to IMO Resolution A.753(18).

Low Flame Spread
The piping system is approved to Low Flame Spread, according to ASTM D635-97 (accepted as an alternative to IMO Resolution A.653(16)).

Smoke Generation & Toxicity
The Smoke Generation & Toxicity characteristics of the piping system has not been evaluated.

Conductivity testing to be carried out on installed system.

Approved mounting/joining specification to be followed.

Type Approval documentation

Tests carried out

Type Testing carried out according to **Type Approval documentation**.

Marking of product

The pipes and fittings are to be marked. The marking shall at least include the following information:
- *manufacturer's name*
- *manufacturing plant*
- *type designation*
- *pressure rating*
- *temperature rating*
- *nominal pressure*
- *dimensions*
- *production date.*

The marking is to be carried out in such a way that it is visible, legible and indelible. The marking of product is to enable traceability to the DNV GL Type Approval Certificate.

Periodical assessment

The scope of the Periodical Assessment is to verify that the conditions stipulated for the Type Approval is complied with and that no alterations are made to the product design or choice of materials.

Periodical Assessment to be performed after 2 and 3.5 years (Certificate Retention) and at renewal after 5 years (Certificate Renewal).

The main elements of the Periodical Assessment are to:

- Ensure that **Type Approval documentation** is available.
- Review design, materials, production process, and performance with respect to possible changes, in order to ensure compliance with **Type Approval documentation** and/or referenced material specifications.
- Ensure traceability between manufacturer's product marking and the DNV GL Type Approval Certificate.

END OF CERTIFICATE