DNV·GL

Certificate No:
TAS00001JH

TYPE APPROVAL CERTIFICATE

This is to certify:

That the Lifting set for Offshore containers and Portable Offshore Units

with type designation(s)
Wire Rope Lifting Sets for Offshore Containers and Portable Offshore Units

Issued to
SSCS Lifting
GREAT YARMOUTH, United Kingdom

is found to comply with
DNV GL standard DNVGL-ST-E271 – 2.7-1 Offshore containers, August 2017
DNV GL standard DNVGL-ST-E273 – 2.7-3 Portable offshore units, December 2016
ISO 10855-2:2018 Offshore containers and associated liftings sets – Part 2: Design, manufacture and testing of lifting sets
EN 13414-1 Wire rope slings
IMO/MSC Circular 860

Application :

1, 2, 3 and 4 leg lifting sets, with forerunner where fitted, for lifting of:
- Offshore Containers, with Maximum Gross Mass 0 to 25000 kg,
- Portable Offshore Units.

Issued at **Aberdeen** on **2018-07-06**
This Certificate is valid until **2023-07-05**.
DNV GL local station: **Great Yarmouth**

Approval Engineer: **Elisabeth Legg**

for **DNV GL**

Alex Doig
Team Lead

This Certificate is subject to terms and conditions overleaf. Any significant change in design or construction may render this Certificate invalid.
The validity date relates to the Type Approval Certificate and not to the approval of equipment/systems installed.

© DNV GL 2014. DNV GL and the Horizon Graphic are trademarks of DNV GL AS.

Product description

This Type Approval Certificate replaces DNV GL Type Approval Certificate No. S-8294.

The Type Approval Certificate covers wire rope lifting sets assembled by SSCS Lifting. These shall be assembled in accordance with DNVGL-ST-E271 or DNVGL-ST-E273.

The wire rope lifting sets assembled by SSCS Lifting consist of components from the following sub suppliers:

Component	**Sub supplier** *(DNV GL to be informed and review all new sub suppliers)*	**DNV GL TAC No.**
Master Link and Quad assembly	Scaw South Africa (Pty) Ltd.	TAS000013Z
Wire rope [1)]	Usha Martin UK Ltd. AP Lifting Gear Company Denwire Pfeifer Drako	n/a
Shackles [2)]	Van Beest BV Crosby Group LLC	TAS000011V TAS00000HA
Ferrules [3)]	Talurit Sahm Splice	n/a
Thimbles [4)]	Sahm Splice George Taylor & Co. Lifting Gear (Midlands) Ltd. AP Lifting Gear Company	n/a

1) Wire ropes used in fore runner and bottom legs of lifting sets shall be 6-stranded and of type 6x19 or 6x36 and may be fibre cored or steel cored, with wire rope grades 1770 N/mm^2 or 1960 N/mm^2, in accordance to EN 12385, or equivalent.
2) Shackles are only considered part of the lifting set if captive (i.e. can not be removed after assembly of lifting set).
3) Ferrules/sleeves shall be in accordance with EN 13411-3, or equivalent.
4) Thimbles shall be in accordance with EN 13411-1, or equivalent.

Components shall be delivered with the following certificates:

- Master Links, Quad assemblies and Shackles: Certificates based on DNV GL Type Approval.
- Wire Ropes: To be supplied with traceable material certificates in accordance with EN 10204, inspection certificate, type 3.1.
- Thimbles and ferrules: To be supplied with a material certificate in accordance with EN 10204, test report, type 2.2.

Application/Limitation

For each delivered drum of wire rope, a test leg with one eye in each end to be prepared and tested to breaking. A reference should be made to the wire drum test report in each lifting set certificate where that wire is used.

All production testing should be carried out according to SSCS Lifting internal procedures and to be agreed with the local DNV GL office.

The manufacturer shall issue product certificates in accordance with DNV GL-ST-E271 Section 8.5, using the certificate form GD012 Rev. 000. This certificate form is only to be used for lifting sets certified in accordance with this Type Approval Certificate.

The WLL to be used in certificates and marked on lifting sets shall be the maximum working load limit (WLL) of the lifting set, as per the definition in DNVGL-ST-E271.

For lifting sets manufactured in accordance with DNVGL-ST-E271
Lifting sets shall be assembled according to the strength requirements described in DNVGL-ST-E271 Section 8. The angle of the sling legs from vertical should be taken into account when choosing slings. This angle should normally be 45°, but smaller angles may be used.

Special lifting sets, assembled according to the principles described in DNVGL-ST-E271 Section 8 and Appendix E, are also covered by this Type Approval. If unsymmetrical slings are to be assembled, the local DNV GL office shall be contacted to review each case, unless otherwise agreed in advance.

> *Note: The sling leg is not necessarily the weakest part of the lifting set. Master Link assemblies selected for lifting sets with legs at 45° may not be suitable for lifting sets with a smaller angle.*

For lifting sets manufactured in accordance with DNVGL-ST-E273
Prior to selection of the lifting set, the minimum required working load limit (WLL) shall be calculated in accordance with the strength requirements in DNVGL-ST-E273 Section 7.3. The Resulting Sling Force (RSF) is provided in the DNV GL Design Verification Report (DVR) for the Portable Offshore Unit. The DVR should be made available for the lifting set manufacturer.

Type Approval documentation

Tests carried out

Prototype breaking load test of assembled wire rope sling leg.

Marking of product

For lifting sets manufactured in accordance with DNVGL-ST-E271: refer to Section 8.
For lifting sets manufactured in accordance with DNVGL-ST-E273: refer to Section 7.6.

Periodical assessment

In order to maintain the validity of the type approval certificate, periodical assessments should be carried out every 12 months.

END OF CERTIFICATE