Certificate No:
**TAS000030H**

# TYPE APPROVAL CERTIFICATE

## This is to certify:

**That the Cargo Securing Devices**

with type designation(s)
**Welding Cone AJ-A1**

Issued to
**General Lashing System (China) Co., Ltd.**
**Ningbo**, **China**

is found to comply with
**DNV GL rules for classification – Ships**

## Application :

**Product(s) approved by this certificate is/are accepted for installation on all vessels classed by DNV.**

**SWL, shear (kN) 210**

Issued at **Hamburg** on **2021-04-27**
This Certificate is valid until **2026-04-26**.
DNV local station: **Ningbo FIS**

for **DNV**

Approval Engineer: **Mark-Oliver Wobig**

**Andree Orth**
**Head of Section**

This Certificate is subject to terms and conditions overleaf. Any significant change in design or construction may render this Certificate invalid.
The validity date relates to the Type Approval Certificate and not to the approval of equipment/systems installed.

LEGAL DISCLAIMER: Unless otherwise stated in the applicable contract with the holder of this document, or following from mandatory law, the liability of DNV AS, its parent companies and their subsidiaries as well as their officers, directors and employees ("DNV") arising from or in connection with the services rendered for the purpose of the issuance of this document or reliance thereon, whether in contract or in tort (including negligence), shall be limited to direct losses and under any circumstance be limited to 300,000 USD.

## Product description

Welding Cone

## Application/Limitation

| Load | Shear [kN] |
|---|---|
| Test Load | 315 |
| Breaking Load | 420 |

Tests to be carried out:

- Production testing: At least 2% of the items delivered are to be selected and subjected to the test load.
- Material tests are to be included energy testing at -20°C, with the impact energy requirements acc. to DNVGL-CP-0068. The material shall be according to the approved drawings. Material certificates shall be 3.1 acc. to ISO 10474:2013.

## Type Approval documentation

| Drawing No. | Rev. | Title |
|---|---|---|
| AJ-A1 | A | Welding Cone |

Drawing approval No. 261.1-033915-1 Date: 2020-09-03
Test report General Lashing dated 2021-04-02

### Tests carried out

The prototype test was carried out in Ningbo, P.R. China, dated 2021-04-02 in accordance with the DNVGL-CP-0068.

## Marking of product

Each item shall be marked by manufacturer for traceability.

## Periodical Assessment

For retention of the Type Approval, a DNVGL surveyor shall perform a survey after 2 and 3.5 years, to verify that the Type Approval is complied with.